Meeting Date: 12/21/2018

Number of Applications Scheduled: 5

| • | 12,21,2010 | | | | | | Number of Applications Scheduled: 5 | |
|----------|-------------------------------------|--|------------|--------------------|---|--------------------------|--|--|
| App No | Applicant | Location Description | County | Stream | Project Description | LMA Endorsement | CEQA Finding | |
| 12817-1 | Reclamation District No. 784 | The project is located east of Highway 70, on the left (east) levee of Best Slough in the community of Plumas Lake, Yuba County. | Yuba | Best Slough | To replace the existing 18-inch diameter corrugated metal storm drain gravity pipe with an 18-inch diameter by 3/16" wall thickness corrosion proof welded steel pipe, in the left (east) levee of Best Slough. The improvements will also include new inlet structure with trash rack, outfall structure with 18-inch diameter automatic drainage gate, riprap apron, and facility markers. The existing pipe was permitted under permit no. 12817 GM. | Reclamation District 784 | The Board has determined that the project is categorically exempt from CEQA under a Class 2 Categorical Exemption (CEQA Guidelines Section 15302) covering replacement or reconstruction of existing structures and facilities where the new structure or facility will be located on the same site with the same purpose as prior structures and facilities and under a Class 3 Categorical Exemption (CEQA Guidelines Section 15303) covering construction of small structures or facilities. | |
| 13387-1 | CA Department of Water Resources | The project is located on the northwestern levee of Sherman Island, on the west Sherman Island Road, and 1.08 miles west of State Hwy 160 in Sacramento County. | Sacramento | Sacramento River | To install a self cleaning fish screen, a maintenance structure and walkway, part of the Sherman and Twitchell Island Fish Screen Project. This location will have the ability to retrieve the fishscreen using a track and electric winch powered by a portable generator. The structure will be supported on a pile foundation. | Reclamation District 341 | The Board, as a responsible agency under CEQA, has reviewed the Initial Study/Mitigated Negative Declaration (IS/MND) (SCH Number: 2016032007, March 2016) and Mitigation Measures for the Sherman and Twitchell Islands Fish Screen Project prepared by the Department of Water Resources as the lead agency. These documents including project design may be viewed at the Board and Department of Water Resources offices. The Department of Water Resources determined that the project would not have a significant effect on the environment and filed a Notice of Determination on April 15, 2016 with the State Clearinghouse. Staff finds that although the proposed project could have a potentially significant effect on the environment, there will not be a significant effect in this case because revisions in the project have been made by or agreed to by the project proponent. The project proponent has incorporated mandatory mitigation measures into the project plans to avoid identified impacts or to mitigate such impacts to a point where no significant impacts will occur. These mitigation measures are included in the project proponent's IS/MND and address impacts to biological resources, cultural resources, hazards and hazardous materials. The description of the mitigation measures are further described in the adopted IS/MND. | |
| 7634-A-1 | Bill Wallace Sr | The project is located 1.24 miles west of the intersection of Sachreiter Basin Rd and Sycamore Slough Rd, north of Arbuckle, Colusa County. | Colusa | Colusa Basin Drain | To replace the existing 24-inch diameter irrigation steel pipe with a 24-inch diameter by 3/8" wall thickness epoxy coated steel pipe, in the left (west) levee of Colusa Drain Canal. The pipe to be replaced from the pump on the water side of the levee to 10 ft. beyond the levee toe on the land side. Additionally, a siphon breaker and a gear operated positive closure device will be installed. The existing pump and irrigation pipe were permitted under permit no. 7634 and 7634-A. | Sutter Maintenance Yard | The Board has determined that the project is categorically exempt from CEQA under a Class 2 Categorical Exemption (CEQA Guidelines Section 15302) covering replacement or reconstruction of existing structures and facilities where the new structure or facility will be located on the same site with the same purpose as prior structures. | |
| 8108-A-1 | Cheryl & William McClendon | on landward slope, of the left bank levee at 692 Riverside Way about 1/4 mile downstream from Brickyard. Section 28, T. 8 N., R. 4 E., M.D.B.&M., Sacramento County. (Levee Mile 3.26 to 3.27, Maintenance Area No. 9) | Sacramento | Sacramento River | This is a name change permit only and includes conditions that are consistent with current flood control standards and policies of the Central Valley Flood Protection Board. This permit supplements permit no. 8108-A that was issued to Robert Yoho on August 11, 1972, to construct a pool within 8 feet of the landward levee toe and to install a six-foot fence landward of the levee toe and to plant ice plant. | Maintenance Area 9 | The proposed action is a name change and not a "project" pursuant to the Public Resources Code Section 21065 and CEQA Guidelines Section 15378(a) covering projects. | |
| 8108-B-1 | Cheryl & William McClendon | on the landward slope of the levee on the left bank of the Sacramento River downstream of the brickyard. Section 28, T. 8 N., R. 4 E., M.D.B.&M., (Maintenance No. 9, Levee Mile 3.26-3.27) Sacramento River, Sacramento County. | Sacramento | Sacramento River | 'This is a name change permit only and includes conditions that are consistent with current flood control standards and policies of the Central Valley Flood Protection Board. This permit supplements permit no. 8108-B that was issued to Robert Yoho on May 5, 1978, To construct a cinder block retaining wall at the toe of the slope and a sprinkler system and cinder block steps | Maintenance Area 9 | The proposed action is a name change and not a "project" pursuant to the Public Resources Code Section 21065 and CEQA Guidelines Section 15378(a) covering projects. | |